Superior Standard

"Sandstone Colonial" Inclusions

BRISBANE, GOLD COAST & SUNSHINE COAST



We build Real Queenslanders

& Sandstone Colonials

External Feature	es:
Brickworks	GB Masonry "Smooth Finish" 100mm series blocks (Sydney Blend) to main wall areas. "Rockface" blocks quoined to all corners. (Option: "Rough sawn with picture frame" as displayed. Also available without picture frame.)
Entrance Door	Solid Cedar 4 panel "Cricket Bat" door. Cedar sidelights included where shown on plan.
French Doors	Solid cedar colonial doors (FP2) with Legge polished brass rim locks
Guttering	
Hot water Unit	Rennai Infinity 25 (option: Temperature controllers & Smart start system)
Insulation	Ceiling: 2.5r Batts. External Walls (ALL): 1.5r Batts. Sisalation to roof over internal areas and
	external walls.
Kitchen Door	
Laundry Door	Corinthian "7A" ½ glass door with VJ feature panel.
Painting	House fully painted inside (4 colours) and outside (3 colours) with premium grade paint.
Portico	Not Included.
Posts	100 x 100 posts in galvanised steel brackets to verandah areas.
Roof	Corrugated Zincalume @ 30 degree pitch unless otherwise stated (Option: Colorbond*).
Roof Ventilator	Large colonial ventilator.
Taps	2 External house taps
Verandah Brackets	Not Included.
Verandah Flooring	Concrete
Verandah Roof	Skillion with extra height above verandah flooring. This reduces closed in feeling and is cooler.
Windows	Double hung aluminium with timber external mouldings. Keyed alike window locks.
Window Hoods	Over external windows to side elevations or as shown on plan.

		and a
Interna	- Genera	Features:

Archways	Plaster Hallway arch - No. 4 Eliptical
Ceiling Height	2.7m (9 foot) ceilings. Some designs have sloping ceilings adjacent to verandah areas to achieve
	traditional look
Cornice	55mm traditional cornice.
Flooring	
Internal Doors	Hume HAG 12 VJ Doors.
Internal Door Furniture	Gainsborough "Metalline" series handles.
Internal Linings	Plasterboard to walls and ceilings throughout except Bathroom & Ensuite (Villaboard).
Linen & Pantry	Both built by carpenter with four shelves and timber trims.
	Lane or Gainsborough Brass finish.
Mouldings	Skirting: 140x18mm CSR architectural Traditional Victorian.
, i	Architraves: 68x18mm CSR architectural Traditional Victorian.
***************************************	Architrave Blocks: 68x22mm Finlaysons Typical to passage way doors as displayed.

Internal - Electrical Items:

Robes Bank of 4 shelves. Chrome hanging rail.

ĺ	Light Points 1 light point per room and hallways plus 4 external wall light points.
	Meter BoxOne including circuit breakers and residual current device connected to all power points;
	Power PointsBED 1: 3 double power points, KITCHEN: 2 double and 3 single, and 1 double per room elsewhere.
-	Smoke detectorsHard wired and adequate number to Australian standards;
	SundryTelephone sockets x1, TV points x2

Superior Standard "Sandstone Colonial" Inclusions

Garth Chapman's
TRADITIONAL
QUEENSLANDERS

We build Real Queenslanders

& Sandstone Colonials

BRISBANE, GOLD COAST & SUNSHINE COAST

Bath	
Furniture	Linkware designer range towel rails and toilet roll holder.
Laundry	Tub: 45 litre stainless steel with white lower cabinet. Taps: Linkware C/P Designer Range.
Mirrors	
	Semi frameless with pivot door.
Taps	Linkware designer range.
Toilet Suite	
Vanity Units	Laminated tops with 2 doors and 3 drawers. Mirror over length of vanity.
*	
Internal - Kitcl	hen Features:
Cupboards	Laminated to selection with overhead cupboards & walk in pantry where indicated on plan.
·	1 bank of 4 drawers and 2 pot drawers.
	(Options: You may upgrade your kitchen to any standard or finish direct with our cabinetmaker*)
Appliances	
, ,	Dishwasher: Provision for client supply. Cold water tap and single power point provided.
	Oven: SMEG - 60cm Stainless steel multi function electric oven
	Rangehood; SMEG - 60cm stainless steel canopy rangehood
Sink	
Taps	Elegance Delux sink mixer with handshower
Internal - Tilin	g:
	\$35/m2 PC allowance for all wall and floor tiles to wet areas;

Preliminaries & General Items:

Toilet......Skirting tile;

Laundry......2 tiles above tub, skirting elsewhere;

Soap Holders Ceramic white to showers;

Internal - Wet Area Features:

	Colour ConsultantConsultation	included.
	Fixed price contractQueensland	Master Builders Association (QMBA) fixed price contract.
	FoundationsConcrete Sla	based upon "S" soil classification. Verandah post piers: 900mm deep x 350mm diameter.
-	GuaranteesSix-year structure	tural guarantee and Six-month maintenance guarantee.
İ	InsurancesAll required b	y Building Services Authority (BSA) and Workplace Health & Safety included.
	ServicesProfessionally	prepared home design to wind loading N3 (W41) as per Australian standards.
	All standard of	ouncil fees including building application fees, stormwater and sewerage fully connected up
	to 10 metres	from main, water connection by local council (PC \$600).
	Soil test, con	our survey, mandatory land searches, and professional foundation design also included.
	Siteworks Up to 300mm	cut over building platform
1	Termite Protection Treated fram	ne. Termimesh to perimeter of internal areas and all penetrations

Please visit our web site for more detailed information and photographs. Garth Chapman is constantly reviewing our policies, procedures, and building specifications in order to provide the best possible products and services. Due to this process we reserve the right to alter these specifications without notice. *All Options will incur additional costs.